



# SNIA

STORAGE NETWORKING INDUSTRY ASSOCIATION

EDUCATION

## "XAM" The Next Interface Standard - Empowering the Application through ILM

David Martin

IM Product Line Mgr, Hewlett Packard

Co-Chair eXtensible Access Method (XAM) Initiative

**Storage Networking Industry Association (SNIA)**

# XAM – What is it??


## eXtensible Access Method (XAM)

- Defined standard interface (i.e. API)
- Between “Consumers” (application and management software)
- and “Providers” (storage systems)
- of *Fixed Content* storage services
- a SNIA Initiative

# Fixed Content

... is **BIG** and **GROWING FAST!**

- Most new digital content is 'born' fixed
- Transactional data is archived, becomes fixed
- Federal regulations impose discipline  
e.g. content retention, disposition
- Fixed / Variable Data
  - 80% / 20% base (est)
  - 90% / 60% growth rate (est)




Source: Hal Varian, UC Berkeley

# XAM Value Proposition

The industry will benefit from a standardized access method to Fixed Content

## Applications Vendors want:

- Annotate data with associated Metadata
- Indicate basic storage management policies
- Speak same language to all types of devices
- Choices between storage vendors
- Manipulate billions if not trillions of “records”




## End Users want:

- Choices between Application Vendors
- Choices between Storage Vendors
- Easy migration between vendors/technology
- Compliance, Scalability, Performance, \$/GB, TCO

## Storage Vendors want:

- Application Support for their Products
- Efficiently Store Application Data and Metadata
- Integrate Basic Storage Management Capabilities
- Manage billions if not trillions of “records”


# XAM Genesis



(\*) SNIA Technical Council Member

© 2006 Storage Networking Industry Association. All Rights Reserved.

# XAM Milestones



# What XAM Provides



- Interoperability
  - XAM-compliant applications works XAM storage systems from any vendor
  - Rich metadata allows multiple applications to share information
  - Information can be migrated between XAM systems through standard import/export operations
- Compliance
  - Integrated record retention and disposition metadata
- ILM Practices
  - Extensible metadata allows for external data classification, annotation
  - ILM policy recorded in standard fields
  - ILM practices implemented by XAM storage system or third-party
- Universal Access to data
  - Application independent store and retrieve
  - Application independent query interface

# XAM Services

- **Store / Retrieval Interface**
  - Metadata & streams storage via XSet abstraction
  - Create, read, update, delete data
- **Search / Query Interface**
  - Based on SQL “Select” statement
  - Supports query of metadata (mandatory) and content (optional)
- **Security Interface**
  - Role-based access control (RBAC)
  - ACL permissions on objects
- **Management Services Interface**
  - Retention
  - Litigation hold
  - Storage management (storage tiers, etc)

# Query / Discovery Examples



## Query & Discovery

- Structured metadata query allows SQL-like flexibility in examining typed fields such as numbers and dates
- Unstructured stream query allows vendor extensibility for full-content search, with annotated information type


## Application examples:

- "Find all records for patient X after 4/7/2006"
- "Create thumbnails of all JPEG files written by application X larger than 300K"

## Query example:

- **SELECT WHERE org.nema.medical.patient\_name="X" and org.nema.medical.record\_date>"4/7/2006"**



# XAM Architecture




- **An application uses the xam.dll to ‘connect’ to a specified XSystem.**
  - An single application may connect to multiple XSystems simultaneously
  - Multiple applications may connect to a single XSystem simultaneously
- **An XSystem is not identical to a vendor’s “storage box”, but a logical abstraction which should be viewed as ‘bag of storage’.**
- **The application may be required to authenticate at the time the connection to an XSystem is established.**
- **The application uses xam.dll to store/retrieve “content objects” to/from the XSystem.**
- **These “content objects” are bundles of data and metadata, and are called XSets.**

# XAM Software Development Kit


- XAM API to be standardized by SNIA
- XAM SDK presents the XAM API to all applications
  - Open Source
  - Governed independently of any vendor
- VIM: Vendor Implementation Module
  - Connects the SDK to a particular storage device through the VIM Interface
  - Provided by device vendor
- SDK Includes (date tbd)
  - Reference VIM
  - Best Practices
  - Sample Application(s)



# XAM Software Development Kit



# XSET Concept



**XSets contain “Streams” and “Properties” that are collectively called “Fields”**


**A property (metadata) is a simple type (i.e. integer, float, string)**

**Streams are “just” a sequence of bytes. Streams can be typed or un-typed**

**Each Field has a name, type, & size**

# Examples

## Mapping Data Types to XSets



# Access to XAM SDK Components

Public Access Component	Access
XAM API Spec	Public access
XAM Library	Public access?
Vendor Implementation Module (VIM)	Storage Vendor
Best Practices guide	Public access

SNIA Component	Notes	Access
XAM Contribution	Steering of specification & implementation	SNIA Membership
XAM Certification/Seal		SNIA Membership
Validation Suite		SNIA Membership
Convenience toolkit	Ease-of-use toolset	SNIA Membership

Preliminary Information - XAM SDK component access details are still being defined

# End Users – Compelling Reasons to Join SNIA



- Get involved & make your voice heard! Join the SNIA End User Council (EUC)
- Assist in review of SNIA Working Group specifications and initiative roadmaps
- Make your views known via SNIA speaking engagements

# Application Vendors - Compelling Reasons to Join SNIA



1. You benefit from the SNIA publicity engine - visibility at SNW, EIW, SNIA Symposiums, InfoStor Road Shows, International SNIA (Europe, Africa Middle East, Asia Pacific, Americas)
2. Your company will be positioned as a technology leader via membership in the SNIA XAM Application Developer Early Adopter Program
3. As XAM Initiative member you can influence direction of the evolving specification, test harness development, conformance and interoperability programs
4. Contribute Code (tools and convenience functions)

# XAM Software Development



- All SNIA software is developed within a gated community
  - you need to be a member of the SNIA to contribute code.
  - SNIA Membership fees for Application developers are based on the current SNIA membership fee model - revenue size and voting/non-voting status.

# Conclusion: XAM

- A common storage API for applications that allows storage vendor specific implementations
  - Many apps to many storage devices
- A new access method to address
  - Scalability to trillions of XSETs
  - Longevity of objects
  - Metadata to capture application intent
- Simple yet powerful
  - Architected for extension

# Where To Go

- SNIA XAM Home
  - <http://www.snia-dmf.org/xam/index.shtml>
- SNIA FCAS TWG  
(XAM Technical WorkGroup)
  - <http://www.snia.org/apps/org/workgroup/fcastwg/>
- CAS Community
  - <http://www.cascommunity.org>
- Your Presenter
  - [david,martin@hp.com](mailto:david,martin@hp.com)



SNIA

STORAGE NETWORKING INDUSTRY ASSOCIATION

EDUCATION

Thank You!